


NOTES:

1. THE CONCRETE USED SHALL BE PORTLAND CEMENT, AIR-ENTRAINED, CLASS "A" CONCRETE WITH AN AIR CONTENT OF 5%, MIN., TO 7%, MAX., AND A SLUMP OF THREE INCHES, MIN., TO FIVE INCHES, MAX.
2. ALL CONCRETE SIDEWALK REPLACEMENT SHALL BE TO FULL PANEL LIMITS, PARTIAL PANEL REPLACEMENT SHALL NOT BE ALLOWED.
3. ALL SIDEWALKS SHALL BE FINISHED WITH A MAGNESIUM FLOAT FINISH UNLESS DIRECTED OTHERWISE BY THE CITY.
4. ALL CURBING SHALL BE RESET OR REPLACED AS REQUIRED, IN ACCORDANCE WITH THE CITY DETAILS.
5. EXPANSION JOINTS TO BE PLACED BETWEEN ADJACENT SLABS, AT BUILDING LINE, AT CURBS, OR AT PENETRATING STRUCTURES.

NO SCALE



Gerald D. Jennings, Mayor
 Randall J. Milano, P.E., City Engineer

CITY OF ALBANY DIVISION OF ENGINEERING
 STANDARD DETAILS

DETAIL NAME:

SIDEWALK REPLACEMENT
 DETAIL

DETAIL No.

SW-2

FILE NAME:

SW-2.DWG

DATE ISSUED

05/01/02

REVISION DATE

06/01/10